

DATE: 09.24.2015

TO: ProTrak

FROM: Bill McDow
Transportation Planning

910 341-3258
910 341-7801 fax
www.wilmingtonnc.gov
Dial 711 TTY/Voice

■ GOOD SHEPHERD CENTER [TRC Plan Review]

Initial Review Note


All comments are based on adopted policy documents, specific City of Wilmington Land Development Code (CofW LDC) and City of Wilmington Technical Standards and Specifications Manual (CofWTSSM) requirements in effect at the time of this review. These have been noted after the comment as appropriate for your ease in further research.

The City Engineer may administratively approve dimensional variance requests per LDC Sec. 18-348. If the Applicant feels further interpretation is in order, please contact Transportation Planning directly to discuss in additional detail. Please apply for all administrative variances in writing, an email is acceptable or this may be included on the plan set. Please see Sec. 18-348 of the Land Development Code for the information required to process a variance request.



TECHNICAL STANDARDS – ACCESS (driveway, sidewalk, and sight distance):

1. Driveways shall be City-standard ramp-type driveways. Show appropriate City standard detail(s) on plan. [Chapter VII ,Detail SD 8-02 (curb) CofWTSSM]
2. Dimension driveway widths and tapers. [Sec.18-529 CofW LDC]
3. The minimum two-lane driveway width is 23'. [7-9 CofW Tech Stds]
4. Provide a sidewalk connection between the site and the public sidewalk.
5. The site plan does not provide a sidewalk for Lake Shore Drive.
6. Provide dimensions for the proposed and existing sidewalk(s).
7. Provide details and dimensions for the proposed Mulch Trail.
8. Provide sidewalk detail SD 3-10 on the plan.
9. Show and apply the City's 20'x70' sight distance triangle at each driveway on the site plan and landscaping plan. [Sec.18-529(c)(3)CofW LDC] Add a note indicating that all proposed vegetation within sight triangles shall not interfere with clear visual sight lines from 30"-10'. [Sec.18-566 CofW LDC]



TECHNICAL STANDARDS – PARKING:

10. The backing stub is to be 10' deep by 15' wide. Please dimension. [\[Chapter VII ,Detail SD 15-12 CofWTSSM\]](#)

TECHNICAL STANDARDS – Barrier Free Design:

11. The 5' sidewalk as proposed where adjacent to 90 degree parking spaces does not meet ADA requirements. An allowance for a 2.5' vehicle overhang must be considered. 4' of the sidewalk must remain clear for pedestrian use. [\[Chapter VII, Detail SD 15-13 CofWTSSM\]](#)
12. Please show location of handicap ramp(s) and signs and provide details on the plan.

GENERAL NOTES TO ADD TO THE PLAN:

- A. All pavement markings in public rights-of-way and for driveways are to be thermoplastic and meet City and/or NCDOT standards. [\[Detail SD-13 CofW Tech Stds\]](#)
- B. All signs and pavement markings in areas open to public traffic are to meet MUTCD (Manual on Uniform Traffic Control Devices) standards. [\[Detail SD 15-13 CofW Tech Stds\]](#)
- C. All traffic control signs and markings off the right-of-way are to be maintained by the property owner in accordance with MUTCD standards.
- D. All parking stall markings and lane arrows within the parking areas shall be white.
- E. A utility cut permit is required for each open cut of a City street. Note this on the plan and contact 341-5888 for more details. In certain cases an entire resurfacing of the area being open cut may be required.
- F. Any broken or missing sidewalk panels, driveway panels and curbing will be replaced.
- G. A landscaping plan indicating the location of required street trees shall be submitted to the City of Wilmington Traffic Engineering Division and Parks and Recreation Department for review and approval prior to the recording of the final plat. [\[SD 15-14 CofW Tech Stds\]](#)
- H. Contact Traffic Engineering at 341-7888 forty-eight hours prior to any excavation in the right of way.

MISCELLANEOUS:

- ❖ Permitting of business identification signage is a separate process. City of Wilmington will not allow obstructions within the right of way.
- ❖ Contact Alina Jakubcanin at 341-7888, Alina.Jakubcanin@wilmingtonnc.gov , to discuss street lighting options.
- ❖ Transportation Planning Staff will review the landscape plan once submitted for compliance with sight distance requirements.
- ❖ Include appropriate City of Wilmington approval stamps prior to submitting final plans.

Please let me know if you have any questions or if I can be of further assistance as this development moves through the review process.